

RE: ESTIMATE BUDGET FOR PLANTING, FENCING AND MAINTENANCE OF 10,000 TREES IN NGONG HILLS FOREST.

1. SITE PREPARATION AND PLANTING.

S/NO	ACTIVITY	UNIT	QUANTITY MANDAYS	UNIT COST KSH	TOTAL COST KSH
1	Clearing of bushes	m/days	200	672	134,400
2	Marking of holes for planting	m/days	110	672	73,920
3	Digging of holes 2ft by 2 ft.	No	10,000	30	300,000
4	Procurement of indigenous tree seedlings	No	10,000	50	500,000
5	Transport of seedlings to the site	No	10,000	3	30,000
6	Planting	m/days	180	672	120,960
7	Supervision and coordination	litres	200	200	40,000
8	Totals A				1,199,280

2. FENCING.

S/NO	ITEMS DESCRIPTION	UNITS	QUANTITY	UNIT COST KSH	TOTAL COST KSH
1	Treated fencing posts 8ft	No	500	850	425,000
2	Chain links 6ft	Rolls	77	3800	292,600
3	Barbed wire	rolls	10	5500	55,000
4	U-nails	Kg	25	300	7,500
5	Ordinary nails 4 "	Kg	10	300	3,000
6	Binding wire	Rolls	4	4000	16,000
7	Cement	Bags	18	800	14,400
8	Sand	Tonnes	10	3500	35,000
9	Ballast	Tonnes	10	3000	30,000
10	Steel gate	No	1		18,000
10	Purchase of water	litres	5000		4,500
10	Transport of materials				60,000
11	Fencing labour	m/days	560	672	376,320
12	Supervision and coordination	litres	200	200	40,000
13	Totals B				1,377,320

3. MAINTENANCE OF PLANTED TREES AT LEAST THREE YEARS

Maintenance will include weeding and beating up (replacement of dead trees). the activity will take a period of three years when the trees will have established well and can continue to grow on their own. Weeding will be done three times a year for 3 years. Watering of the planted trees will be required during the dry spelt period.

S/NO	ACTIVITY	UNIT	QUANTITY/ MANDAYS	UNIT COST KSH	TOTAL COST KSH
1	Weeding	m/days	1125	672	756,000
2	Beating up	m/days	140	672	94,080
3	Tree seedlings procurement	No	2000	50	100,000
4	Purchase and installation of 10,000 litres water tanks	No	4	125,000	500,000
5	Horse pipes 50m	Rolls	6	7000	42,000
6	Water purchase in bowzers	No	240	6000	480,000
7	Watering labour	m/days	1200	672	806,400
	Total C				2,778,480
	Totals A+B+C				5,355,080